

BRUHAT BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Executive Engineer Dasarahalli Division B.B.M.P, Bangalore - 73

SCHEDULE - B

Name of the Work : Providing SS Railing and MS Gate For Indira canteen at pipeline road in Ward no 13

Sl. No.	Description	Unit	Qty	Rates	
				In Figures	In Words
1	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specification and directions of engineer in charge of the work	Sqm	8.80	3150.00	Three Thousand One Hundred Fifty Only
2	Providing and fixing 304 - grade stainless steel hand rails of 14-gauge pipes for Ramps staircase made out of stainless steel hallow pipes, using 50mm dia for verticals @1.60 mtr c/c fixed tot he ramps or steps by drilling with bolts and 100mm dia MS base plates 10mm gauge for fixing of Vertical pipes 4 - Nos anchor bolts & 40mm dia pipes fixed horizontally for 2-rows top, one pipes fixed with vertical pipes another one fixed with elbows and 25mm dia pipes are fixed horizontally for 2-rows below top measure @ equal intervals including cutting, welding, bending wherever necessary with suitable caps @ tops, bottoms & corners finishing with mat / shining etc , complete including cost and conveyance of all materials, labour for all items ofwork, HOM of equipment with all lead and lift, loading and unloading, transportation charges and all other incidental charges etc., complete as per specification and directions of the Engineer-in-charge of the work.	Sqm	43.62	6250.00	Six Thousand Two Hundred Fifty Only
3	Providing and Fixing Granite Benches Including Cost of material and Labour as per specification and directions of the Engineer-in-charge of the work. (Data Rate Aprooved)	Nos	6	9500.00	Nine Thousand Five Hundred Only

Contractor Signature

Executive Engineer
Dasarahalli Division